## PLANTING NOTES

1. QUANTITIES GIVEN FOR PLANT MATERIALS SPECIFIED FOR "ON CENTER" SPACING ARE SHOWN FOR CONVENIENCE ONLY AND ARE 14. ALL PLANTING AREAS SHALL BE LOOSENED TO A DEPTH OF 8". APPLY 4 C.Y. OF ORGANIC AMENDMENT AND 15 LBS. SUBORDINATE TO THE SPACING GIVEN. VERIFY AND SUPPLY SUFFICIENT NUMBER OF PLANTS TO FULFILL SPACING REQUIREMENTS. OF 10-10-10 FERTILIZER PER 1000 S.F. AND BLEND WITH THE TOP 6" OF SOIL. THIS AMENDMENT IS FOR BIDDING PURPOSES, AND

2. ALL HEADER AND BAMBOO ROOT BARRIERS SHALL BE LOCATED BY THE ARCHITECT ON SITE.

3. CONTRACTOR SHALL INSTALL PLANT MATERIAL IN ACCORDANCE WITH THE SPECIFICATIONS, DRAWINGS AND DETAILS.

4. CONTRACTOR SHALL PROVIDE A MAINTENANCE PERIOD OF NOT LESS THAN 90 DAYS COMMENCING AT THE DATE OF FINAL ACCEPTANCE. SUCH MAINTENANCE SHALL INCLUDE ALL CARE PERTAINING TO ALL WORK INSTALLED AS PART OF THESE CONTRACT

5. THE CONTRACTOR SHALL MAINTAIN A QUALIFIED SUPERVISOR ON THE SITE AT ALL TIMES DURING CONSTRUCTION THROUGH COMPLETION OF PICK-UP WORK.

6. THE CONTRACTOR SHALL VERIFY ALL PLANT MATERIAL QUANTITIES LISTED FOR CONVENIENCE OF CONTRACTOR. ACTUAL NUMBER OF SYMBOLS SHALL HAVE PRIORITY OVER QUANTITIES DESIGNATED.

7. REMOVE ALL DEBRIS, WEEDS, EXCESS MATERIAL AND ROCKS LARGER THAN 1" IN DIAMETER FROM PLANTING AREAS PRIOR TO PREPARATION & AGAIN PRIOR TO PLANTING.

8. SEE DETAILS AND SPECIFICATIONS FOR STAKING METHOD, PLANT PIT DIMENSIONS, SOIL PREPARATION, AND BACKFILL REQUIREMENTS.

9. ALL PLANT MATERIALS SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

PENNISETUM SETACEUM / FOUNTAIN GRASS

10. FINAL LOCATION OF ALL PLANT MATERIAL SHALL BE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT. 11. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT 48 HOURS PRIOR TO COMMENCEMENT OF WORK TO COORDINATE PROJECT OBSERVATION SCHEDULES.

12. GROUNDCOVER PLANTING SHALL BE CONTINUOUS UNDER ALL TREES AND SHRUBS. GROUNDCOVER SHALL BE PLANTED ACCORDING TO SPACING ON PLANT LEGEND.

13. TREES SHALL BE LOCATED A MINIMUM OF 5' FROM WALLS, OVERHEADS, WALKS, HEADERS, AND OTHER TREES WITHIN THE PROJECT. IF CONFLICTS ARISE BETWEEN SIZE OF AREAS AND PLANS, CONTRACTOR TO CONTACT LANDSCAPE ARCHITECT FOR RESOLUTION. FAILURE TO MAKE SUCH CONFLICTS KNOWN TO THE LANDSCAPE ARCHITECT WILL RESULT IN CONTRACTORS LIEABILITY TO RELOCATE THE MATERIALS.

DASYLIRON SPP. / DESERT SPOON

SHALL BE SUPERCEDED BY RECOMMENDATIONS OF THE SOIL ANALYSIS REPORT.

15. FOR ALL TREES AND SHURB PLANTING, THE FOLLOWING PREPARED SOIL MIX SHALL BE USED FOR BACKFILL IN THE PLANTERS. THIS MIX IS FOR BIDDING PURPOSES, AND SHALL BE SUPERCEDED BY RECOMMENDATIONS OF THE SOIL ANALYSIS REPORT. SITE SOIL - 6 PARTS BY VOLUME

ORGANIC AMENDMENT - 4 PARTS BY VOLUME SOIL CONDITIONER / FERTILIZER 10-10-10-1LB. PER C.Y. OF MIX

16. TURF IS NOT ALLOWED ON SLOPES GREATER THAN 25% WHERE THE TOE OF THE SLOPE IS ADJACENT TO AN IMPERMEABLE HARDSCAPE..

17. RECIRCULATING WATER SYSTEMS SHALL BE USED FOR WATER FEATURES.

SIGNED

IRON SULFATE - 2 LBS. PER C.Y.OF MIX

18. A MINIMUM 3-INCH LAYER OF MULCH SHALL BE APPLIED ON ALL EXPOSED SOIL SURFACES OF PLANTING AREAS EXCEPT TURF AREAS, CREEPING OR ROOTING GROUNDCOVER, OR DIRECT SEEDING APPLICATIONS WHERE MULCH IS CONTRAINDICATED. 19. FOR SOILS LESS THAN 6% ORGANIC MATTER IN THE TOP 6 INCHES OF SIL, COMPOST AT A RATE OF A MINIMUM OF FOUR CUBIC YARDS PER 1,000 SQUARE FEET OF PERMEABLE AREA SHALL BE INCORPORATED TO A DEPTH OF SIX INCHES INTO THE SOIL. 20. I AGREE TO COMPLY WITH THE REQUIREMENTS OF THE WATER EFFICIENT LANDSCAPE ORDINANCE AND SUBMIT A COMPLETE LANDSCAPE DOCUMENTATION PACKAGE THAT COMPLYS WITH THE PERFORMANCE APPROACH.

21. AT THE TIME OF FINAL INSPECTION THE PERMIT APPLICANT MUST PROVIDE THE OWNER OF THE PROPERTY WITH A CERTIFICATE OF COMPLETION, CERTIFICATE OF INSTALLATION, IRRIGATION SCHEDULE AND SCHEDULE OF LANDSCAPE AND IRRIGATION

ILEX CRENATA / BOX-LEAVED HOLLY

MAINTENANCE.

1. CONTRACTOR IS TO AUGMENT EXISTING IRRIGATION SYSTEM. CONTRACTOR SHALL REPAIR OR REPLACE ANY EXISTING LANDSCAPE AND IRRIGATION DAMAGED FROM CONSTRAUCTION TO AN ACCEPTABLE LANDSCAPE CONDITION WITH A FULLY FUNCTIONAL AND EFFICIENT IRRIGATION SYSTEM PER THE CONTAINED CONDITIONS.

2. ALL NEW TREES REQUIRE INDIVIDUAL POP-UP STREAM BUBBLERS, MIN. 2 PER TREE, WITHIN 4' OF TREE. TREE IRRIGATION SHALL BE ON A SEPARATE VALVE.

TRADESCANTIA PALLIDA / SPIDERWORT

3. SPRAY OR ROTOR HEADS SHALL BE ON POP-UPS: 6" FOR LAWN, LOW GROUNDCOVER OR PARKED CAR OVERHANG AREAS, 12" FOR SHRUB AREAS. HEADS ON RISERS ARE ONLY ALLOWED ADJACENT TO WALLS WITH LIMITED SPACE FOR POP-UPS. 4. LOCATE SPRAY HEADS 24" FROM NON-PERVIOUS PAVING TO PREVENT OVERSPRAY. EXCEPTION ALLOWED IF ADJACENT SURFACE IS PERMEABLE OR IF USING ALTERNATIVE TECHNOLOGY IRRIGATION. ROTATOR OR ROTARY HEADS MAYBE LOCATED 12"

5. CONTRACTOR SHALL REPLACE ANY EXISTING IRRIGATION CONTROLLER WITH A MODULE AND SENSOR TO PROVIDE WEATHER BASED INFORMATIONTHAT WILL AUTOMATE THE IRRIGATION RUNTIMES BASED ON WEATHER. SEE HUNTER SOLAR SYNC, RAINBIRD ET MANAGER OR EQUIVALENT.

6. THE PLANTING AND IRRIGATION SYSTEM SHALL BE COMPLETED BY THE DEVELOPER/BUILDER PRIOR TO THE CLOSE OF ESCROW OF 50 PERCENT OF THE UNITS OF THE PROJECT OR PHASE.

7. SIXTY DAYS AFTER TLANDSCAPE AND IRRIGATION INSTALLATION, THE LANDSCAPE PROFESSIONAL SHALL SUBMIT TO THE HOMEOWNERS/PROPERTY OWNERS ASSOCIATION A CERTIFICATE OF SUBSTANTIAL COMPLETION (12.40 G LAMC.) 8. THE DEVELOPER/BUILDER SHALL GUARANTEE ALL TRESS AND IRRIGATION FOR A PERIOD OF SIX MONTHS AND ALL OTHER PLANS FOR A PERIOD OF 60 DAYS AFTER LANDSCAPE AND IRRIGATION INSTALLATION.

9. PRESSURE REGULATING DEVICES ARE REQUIRED IF WATER PRESSURE IS BELOW OR EXCEEDS THE RECOMMENDED PRESSURE OF THE SPECIFIED IRRIGATION DEVICES. 10. CHECK VALVES OR ANTI-DRAIN VALVES ARE REQUIRED ON ALL SPRINKLER HEADS WHERE LOW POINT DRAINAGE COULD OCCUR.

STATEMENTS AND CERTIFICATION 1. I HAVE COMPLIED WITH THE CRITERIA OF THE ORDINANCE AND APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE


LANDSCAPE DESIGN PLANS. 2. A DIAGRAM OF THE IRRIGATION PLAN SHOWING HYDROZONES SHALL BE KEPT WITH THE IRRIGATION CONTROLLER FOR SUBSEQUENT MANAGEMENT PURPOSES.

ERIOBOTRYA DEFLEXA / BRONZE LOQUAT

3. A CERTIFICATE OF COMPLETION SHALL BE FILLED OUT AND CERTIFIED BY EITHER THE SIGNER OF THE LANDSCAPE PLANS, THE SIGNER OF THE IRRIGATION PLANS, OR THE LICENSED LANDSCAPE CONTRACTOR FOR THE PROJECT.

4. AN IRRIGATION AUDIT REPORT SHALL BE COMPLETED AT THE TIME OF FINAL INSPECTION.

SANSEVIERIA SPP. / MOTHER-IN-LAW'S TONGUE





GARAGE GARAGE

10/31/21 RENEWAL DATE

522 S. VENICE BLVD VENICE, CA 90291

Number **Revision Date** 

Revision Schedule

Revision

LANDSCAPE PLAN

DRAWN **DATE** 9/14/2021 5:51:40 PM

17042